



Sher-e-Kashmir University of Agricultural Sciences and Technology of Jammu

QUOTATION

Quotations are invited from the interested parties/persons through post/currier for execution of work mentioned in “Annexure I” at OFRC, SKUAST-J, Chatha under RKVY project entitled “Composting technology for farm waste management and nutrient recycling”. The quotations should reach this office within 15 days from the date of issuance of this notice. The detailed specifications and quantum of the work can be obtained from undersigned at the office of the Organic Farming Research Centre, SKUAST-J, Chatha during working hours from 9:30 am to 5:00 pm.

Dr. Balbir Dhotra
P. I. (RKVY- CTFN)

No: AUJ/OFRC/20-21/RKVY-CTFN/11-16

Dated: 20/08/2020

Copy to the:

- Director Research, SKUAST-J, Chatha for information
- Estates Officer, SKUAST-J, Chatha for information
- A/c Officer, Estaes division, SKUAST-J, Chatha for information
- Incharge Data Centre for uploading the same on the University website for vide circulation
- Notice board

SKUAST
Jammu

Organic Farming & Research Centre, Chatha, Jammu, J& K 180009, India.

Mob.: +91-7006133255
Email: dhotrabalbir@yahoo.in
Visit us at: www.skuast.org

Annexure I

(to letter no. No: AUJ/OFRC/20-21/RKVY-CTFN/11-16, dated: 20/08/2020)

Name of the work: Construction of vermi-compost shed/unit at OFRC, SKUAST-J, Chatha

S. No.	Work Description	Qty.	Unit	Rates to be Quoted by the contractor (Rs.)
1.	Earth work in excavation by mechanical means/ manual means in foundation trenches or drains including dressing of sides and ramming of bottoms lift upto 1.5m including getting out the executed soil and disposal of surplus executed soil as directed with in a lead of 50 m.	1	cum	
2.	Providing and laying in position cement concrete of specific grade excluding the cost of centering and shuttering. All work to plinth level.			
(i)	1:5:10 (1 cement: 5 coarse sand: 10 graded stone aggregate 40mm nominal size).	1	cum	
(ii)	1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size).	1	cum	
3.	Centering and Shuttering including strutting propping etc removal of form work for.			
(i)	Foundation, footing, bases of columns etc for mass concrete.	1	sqm	
4.	Steel work in built up tabular (round, square or rectangular hollow tubes etc) trusses etc including cutting hoisting fixing in position and applying priming coat of approved steel primer, including welding and bolted with special shaped washers etc complete. Hot finished welded type tubes.	1	kg	
5.	Painting with synthetic enamel paint of approved brand and manufacture. Two or more coats.	1	sqm	

Note: The payment will be released after the completion of above said work.

Signature of the Contractor